

## NOTES:

- 1. BURIED CONDUIT SHALL BE SCHEDULE 40 PVC. EXPOSED CONDUIT TO BE IMC, SCHEDULE 80 PVC, OR RIGID STEEL CONDUIT.
- 2. ALL SWEEPS TO BE MINIMUM OF 24" RADIUS.
- 3. MAXIMUM OF 3 SWEEPS IN SERVICE RUN.
- 4. COMPANY WILL INSTALL AND MAINTAIN UNDERGROUND SERVICE CABLE, PROVIDED THE INITIAL INSTALLATION IS PER COMPANY SPECIFICATIONS.
- 5. METER AND SERVICE LOCATION MUST BE APPROVED BY COMPANY PRIOR TO INSTALLATION.
- 6. CUSTOMER SHALL PROVIDE AND INSTALL ALL TRENCHING, CONDUIT, SHADING, AND BACKFILL PER COMPANY SPECIFICATIONS.
- 7. TRENCH MUST REMAIN UNCOVERED UNTIL INSPECTED BY TEPA.

| REVISIONS | DATE | NAME | APPROVED | C:\Users\dannyc.NETI\Documents\Hy Pictures\TEPApng | RESIDENTIAL SERVICE SPECIFICATIONS |  |  |
|-----------|------|------|----------|--|------------------------------------|--|--|
|           |      |      |          |  | UNDERGROUND SERVICE                |  |  |
|           |      |      |          |  | FROM AN OVERHEAD                   |  |  |
|           |      |      |          |  | FACILITY                           |  |  |